कार्यालय–विश्वविद्यालय अभियन्ता,

दीनदयाल उपाध्याय गोरखपुर विश्वविद्यालय, गोरखपुर-273009 (उ०प्र०)

पत्रांक : 1021/वि0वि0अभि0/2025 दिनॉक : 01/09/2025

अल्पकालीन निविदा सूचना

मा0 कुलपति जी के प्राप्त आदेश के क्रम में एतदद्वारा समस्त सम्बन्धित को सूचित किया जाता है कि विश्वविद्यालय परिसर में निम्नलिखित निर्माण/मरम्मत कार्य हेतु विश्वविद्यालय में पंजीकृत इस प्रकार के सम्पन्न कर रहे सिविल अनुरक्षण कार्यो से सम्बन्धित अद्यतन वैध रजिस्टर्ड ठेकेदारों द्वारा प्रतिशत दर पर निविदा आमंत्रित की जाती है।

क्रम सं0	कार्य का नाम	अनु0लागत (रूपये में)	जमानती धनराशि (रूपये में)	कार्य पूर्ण कराने की समयावधि	निविदा का मूल्य + जीएसटी 18 प्रतिशत + रू0 500.00 स्टेशनरी चार्ज (रूपये में)
1.	विश्वविद्यालय अतिथि गृह स्थित मा0 कुलाधिपति विश्राम कक्ष में अनुरक्षण कार्य	895000.00	44800.00	20 दिन	770.00

कार्यालय–विश्वविद्यालय अभियन्ता,

दीनदयाल उपाध्याय गोरखपुर विश्वविद्यालय, गोरखपुर-273009 (उ०प्र०)

शर्ते :–

1. निविदा दिनांक 01.09.2025 से 09.09.2025 तक 3:00 बजे तक अभियांत्रिक विभाग के कार्यालय से क्रय किया जा सकता है जो निविदा दिनांक 09.09.2025 को वित्त अधिकारी/अभियांत्रिक कार्यालय में निविदा बाक्स में अपरान्ह 05:00 बजे तक डाले जा सकते हैं। दिनांक 10.09.2025 को पूर्वान्ह 11:00 बजे कमेटी कक्ष में क्रय समिति/निविदा समिति की उपस्थिति में निविदादाताओं के समक्ष खोली जायेगी। यदि उक्त निविदा खोलने के दिनांक को राजकीय अवकाश घोषित होता है तो निविदा खोलने की तिथि अगला कार्य दिवस होगा और स्थल तथा खोलने के समय तथा वैधता में कोई परिवर्तन नहीं होगा। निविदा 'टू–बिड सिस्टम' के अनुसार डाला जा सकेगा। तकनीकी बिड में अर्ह होने के उपरान्त ही फर्म/ठेकेदार का वित्तीय बिड खोला जायेगा।
2. निविदा के साथ धरोहर धनराशि जमा करना अनिवार्य है। धरोहर धनराशि शिड्यूल कामर्शियल बैंक की एफ.डी.आर./एन.एस.सी. के रूप में होनी चाहिए जो विश्वविद्यालय के वित्त अधिकारी के पदनाम से बन्धक होगा। बिना धरोहर की धनराशि जमा किये गये निविदादाता के निविदा पर कोई विचार नहीं किया जायेगा। धरोहर धनराशि/जमानत धनराशि संबंधी एफ.डी.आर./एन.एस.सी. की छायाप्रति निविदा प्रपत्र के साथ संलग्न किया जाना आवश्यक होगा तथा उक्त की मूल प्रति निविदा खोलने के समय प्रस्तुत करना अनिवार्य होगा।
3. निविदा प्रपत्र मूल्य दी०द०उ०गो०वि०वि०गोरखपुर के लेखा विभाग से प्राप्त कर मूल रसीद निविदा के प्रपत्र के साथ संलग्न किया जाना आवश्यक होगा।
4. सशर्त निविदाएँ स्वीकार नही की जायेगी तथा निविदादाताओं की दर निविदा खुलने की तिथि से 18 दिनों तक वैध होगी। निविदा के साथ 100.00 रूपये के नान जुडिसीयल स्टाम्प पेपर पर निविदाता को इस आशय का उल्लेख करना होगा कि दिये गये समय के अन्तर्गत कार्य न पूर्ण करने की दशा में उनके द्वारा जमा किया गया जमानत की राशि जब्त कर ली जायेगी ।
5. निविदादाता एवं विश्वविद्यालय के बीच किसी विवाद की स्थिति में अन्तिम निर्णय कुलपति, दी०द०उ०गो०वि०वि० गोरखपुर का होगा जो दोनों पक्षों को मान्य होगा ।
6. अनुबंधित ठेकेदार के द्वारा कार्यादेश के अनुरूप यदि कार्य दिये गये निर्धारित समय से पूर्ण नहीं किया जाता है तो ऐसी दशा में विश्वविद्यालय को विश्वविद्यालय में किसी अन्य पंजीकृत ठेकेदार से कार्य कराने का अधिकार सुरक्षित होगा तथा उसके लिये ठेकेदार के विरूद्ध विधिक कार्यवाही की जायेगी ।
7. अनुबन्ध की शर्तो का पालन करना ठेकेदार के लिये अनिवार्य है तथा उसके किसी भी शर्त एवं अन्य शर्तो का उल्लंघन करने पर ठेकेदार आर्थिक एवं प्रशासनिक दण्ड का भागी होगा ।
8. जमानत राशि के स्थान पर ठेकेदार द्वारा किसी अन्य राशि जो विश्वविद्यालय में अथवा अन्य जगह जमा है, उसे स्वीकारने के लिये निविदा में लिखा जाता है तो वह मान्य नही होगा ।
9. यदि किसी मद हेतु निविदा में दरें अंकित नही हैं तो वह लोक निर्माण विभाग उ०प्र०/केन्द्रीय लोक निर्माण विभाग अथवा दोनों में जो कम हो अनुमोदित दर कहा जायेगा तथा किसी भी दशा में लोक निर्माण विभाग के सेड्यूल दर से अधिक का दर स्वीकार नहीं होगा। निविदा दरें समस्त करों सहित अंकित किया जाना अनिवार्य है।

Raughlendra Gupta

10. बिना कारण बताये कोई एक अथवा समस्त निविदाओं को निरस्त करने का अधिकार विश्वविद्यालय के पास सुरक्षित है।
11. न्यूनतम दर होने के उपरान्त भी यदि कार्य करने का अनुभव नहीं है तो विश्वविद्यालय प्रशासन के पास निविदा निरस्त करने का अधिकार सुरक्षित होगा ।
12. विद्युत कार्य हेतु निविदादाता को निदेशक विद्युत सुरक्षा उ0प्र0 लखनऊ के अन्तर्गत (ए) श्रेणी के पंजीकृत होना तथा निविदा के साथ नवीनतम प्रमाण पत्र संलग्न करना अनिवार्य है।
13. मरम्मत एवं आपूर्ति संबंधित कार्यों हेतु निविदादाता को इस तरह का कार्य का अनुभव होना अनिवार्य है।

निविदादाता को पैन कार्ड, जी0एस0टी0रजिस्ट्रेशन प्रमाण पत्रों की छायाप्रति संलग्न करना अनिवार्य है। अन्यथा निविदा मान्य नहीं होगी। निविदा खोलने के समय पंजीकरण, कार्य अनुभव संबंधी प्रमाण पत्र तथा पैन कार्ड, जी0एस0टी0 रजिस्ट्रेशन संबंधी प्रमाण पत्र मूल रूप में प्रस्तुत करना अनिवार्य होगा। साथ ही संलग्न किये गये निविदा प्रपत्रों की स्व–प्रमाणित प्रति निविदा खोलने के समय प्रस्तुत करना होगा।

14. फर्म या ठेकेदार द्वारा प्रत्येक कार्य के लिए लिफाफे पर कार्य का नाम के साथ तकनीकी बिड एवं वित्तीय बिड अलग–अलग लिफाफे में डाली जायेंगी। एक फर्म या ठेकेदार एक या एक से अधिक निविदायें डाल सकता है।
15. सिविल एवं विद्युत अनुरक्षण कार्य हेतु विश्वविद्यालय में पंजीकृत अद्यतन वैध रजिस्टर्ड ठेकेदारों को ही प्रतिभाग करने का अधिकार होगा।
16. निविदा मूल्य से कम मूल्य पर टेण्डर डाले जाने पर प्रत्येक कार्यों का कामर्शियल बैंक की एफ. डी.आर. / एन.एस.सी. के रूप में अतिरिक्त परफार्मेन्स सिक्यूरिटी (जितने प्रतिशत कम उतनी धनराशि का) जमा करना अनिवार्य होगा।
17. विवाद की स्थिति में सभी विवाद गोरखपुर न्यायालय क्षेत्र में मान्य होगा।
18. अन्य विवरण एवं शर्ते अभियान्त्रिक कार्यालय दी0द0उ0 गोरखपुर वि0वि0 गोरखपुर से किसी भी कार्यदिवस में ज्ञात किया जा सकता है।
19. निविदादाता को इस आशय का शपथ पत्र देना होगा कि उसकी फर्म किसी सरकारी अथवा अन्य प्रतिष्ठित प्रतिष्ठान द्वारा ब्लैक लिस्टेड घोषित नहीं है।

कुलसचिव

Kaushlendra Gupta

कार्यालय–विश्वविद्यालय अभियन्ता,

दीनदयाल उपाध्याय गोरखपुर विश्वविद्यालय, गोरखपुर-273009 (उ०प्र०)

तकनीकी बिड

1. कार्य का नाम ....
2. अनुमानित लागत ....
3. फर्म/ठेकेदार का नाम एवं पता ....
   ....
4. मोबाइल नम्बर ....
5. पंजीकरण का विवरण ....
   (कृपया प्रमाण पत्र की **छायाप्रति संलग्न** करें)
6. धरोहर धनराशि का विवरण (जो वित्त अधिकारी, दी0द0उ0गोरखपुर विश्वविद्यालय, गोरखपुर के पक्ष में बंधक हो) – (कृपया **छायाप्रति संलग्न** करें एवं तकनीकी बिड खोलते समय मूलप्रति उपलब्ध करायें)
   एफ.डी.आर./एन.एस.सी. संख्या..बैंक का नाम ....
   तिथि .... धनराशि ....
7. निविदा मूल्य रू. 770.00 का विवरण
   (कृपया रसीद की **मूलप्रति संलग्न** करें)
   वि0वि0 रसीद की संख्या ....तिथि .... धनराशि ....
8. चरित्र प्रमाण पत्र ....
   (कृपया अद्यतन वैध प्रमाण पत्र की **छायाप्रति संलग्न** करें)
9. हैसियत प्रमाण पत्र ....
   (कृपया अद्यतन वैध प्रमाण पत्र की **छायाप्रति संलग्न** करें)
10. जी.एस.टी. पंजीकरण का विवरण ....
    (कृपया प्रमाण पत्र की **छायाप्रति संलग्न** करें)
11. पैन नम्बर ....
    (कृपया प्रमाण पत्र की **छायाप्रति संलग्न** करें)
12. अनुभव संबंधी विवरण ....
    (कृपया विवरण की **छायाप्रति संलग्न** करें)
13. विगत 3 वर्ष का आई.टी.आर. संबंधी विवरण ....
    (कृपया विवरण की **छायाप्रति संलग्न** करें)
14. ब्लैक लिस्ट न होने का शपथ पत्र ....
    (कृपया विवरण की **छायाप्रति संलग्न** करें)
15. ज्यूडिसियल स्टाम्प पेपर पर इस आशय का उल्लेख कि निर्धारित समय के अन्तर्गत कार्य पूर्ण न करने पर धरोहर की धनराशि जब्त कर ली जायेगी।
    (कृपया घोषणा पत्र मूल रूप में **संलग्न** करें)
16. विद्युत संबंधी कार्य हेतु वांछित प्रमाण पत्र का विवरण ....
    (कृपया विद्युत संबंधी कार्य का लाइसेंस की अद्यतन वैध **छायाप्रति संलग्न** करें)

नोट : कृपया उपरोक्त तकनीकी बिड में दिये गये क्रम संख्या के अनुसार ही संलग्नकों/छायाप्रतियों को संलग्न करने का कष्ट करें।

हस्ताक्षर ....
फर्म/ठेकेदार का नाम ....
मुहर ....

कार्यालय–विश्वविद्यालय अभियन्ता,
दीनदयाल उपाध्याय गोरखपुर विश्वविद्यालय, गोरखपुर-273009 (उ०प्र०)

वित्तीय–बिड

क्रम सं0	कार्य का नाम	अनु0लागत (रूपये में)	जमानती धनराशि (रूपये में)	कार्य पूर्ण कराने की समयावधि	निविदादाता द्वारा कार्य कराने हेतु दरें अंकित करें। (In percentage Below/Above)
1	विश्वविद्यालय अतिथि गृह स्थित मा0 कुलाधिपति विश्राम कक्ष में अनुरक्षण कार्य	895000.00	44800.00	20 दिन	....

1. निविदादाता का नाम ....
2. पूरा नाम ....
3. पता ....
4. मुहर ....
5. मोबाइल नंबर ....
6. हस्ताक्षर ....

दी0द0उ0 गोरखपुर विश्वविद्यालय गोरखपुर
कार्य का नाम – अतिथि गृह।

Summary of Estimated Cost

Sl.No.	Particulars	Amount
1	Cost of Civil Work	715877.70
2	Cost of Electic work	178969.43
	Total	894847.13
	Say in Lacs	8.95

Kaushlendra Gupta

J.E. U.E.

D.D.U. GORAKHPUR UNIVERSITY, GORAKHPUR

Detail of Measurement

Name of work - Repair work for V.VIP Room

Place - अतिथि गृह

S.No.	Item of work	No.	No.	No.	Length	Width	Depth	Quantity	Unit
1	Providing and fixing partition upto ceiling height consisting of G.I. frame and required board, including providing and fixing of frame work made of special section power pressed/ roll form G.I. sheet with zinc coating of 120 gms/sqm(both side inclusive), consisting of floor and ceiling channel 50mm wide having equal flanges of 32 mm and 0.50 mm thick, fixed to the floor and ceiling at the spacing of 610 mm centre to centre with dash fastener of 12.5 mm dia meter 50 mm length or suitable anchor fastener or metal screws with nylon plugs and the studs 48 mm wide having one flange of 34 mm and other flange 36 mm and 0.50 mm thick fixed vertically within flanges of floor and ceiling channel and placed at a spacing of 610 mm centre to centre by 6 mm dia bolts and nuts, including fixing of studs along both ends of partition fixed flush to wall with suitable anchor fastener or metal screws with nylon plugs at spacing of 450 mm centre to centre, and fixing of boards to both side of frame work by 25 mm long dry wall shers, complete as per manufacturer's specification and direction of Engineer-in-charge								
	9.105.3 90mm overall thickness Partition with 8mm thick double skin Calcium Silicate Board made with Calcareous & Siliceous materials reinforced with cellulose fiber manufactured through autoclaving process with Compressive Strength 225 kg/sq.cm, Bending Strength 100 kg / sq.cm	2	2	1	4.27		3.00	51.24	
		2	2	1	3.66		3.00	43.92	
		2	2	1	2.45		3.00	29.40	
		2	2	1	3.05		3.00	36.60	
	Fall Ceiling	2	2	1	4.27	3.66		62.51	
		2	2	1	2.45	3.18		31.16	
		2	1	1	4.20	2.92		24.53	
								279.36	Sq.m
2	9.117 9.118 Providing and fixing sliding arrangement in racks/ cupboards/cabinets shutter with stainless steel rollers to run inside C or E aluminium channel section (The payment of C or E channel shall be made separately) Providing and fixing factory made uPVC door frame made of uPVC extruded sections having an overall dimension as below (tolerance ±1mm), with wall thickness 2.0 mm (± 0.2 mm), corners of the door frame to be Jointed with galvanized brackets and stainless steel screws, joints mitred and Plastic welded. The hinge side vertical of the frames reinforced by galvanized M.S. tube of size 19 X 19 mm and 1mm (± 0.1 mm) wall thickness and 3 nos stainless steel hinges fixed to the frame complete as per manufacturer's specification and direction of Engineer in charge								
	9.117.2 Extruded section profile size 42x50 mm	2	1	1	2.10			4.20	
		2	1	1	1.00			2.00	
		2	2	1	1.50			6.00	
		2	2	1	1.20			4.80	
								17.00	Rm

Kaushlendra Gupta

3	9.118.2 30 mm thick factory made Polyvinyl Chloride (PVC) door shutter made of styles and rails of a uPVC hollow section of size 60x30 mm and wall thickness 2 mm (± 0.2 mm), with inbuilt decorative moulding edging on one side. The styles and rails mitred and joint at the corners by means of M.S. galvanised/ plastic brackets of size 75x220 mm having wall thickness 1.0 mm and stainless steel screws. The styles of the shutter reinforced by inserting galvanised M.S. tube of size 25x20 mm and 1 mm (± 0.1 mm) wall thickness. The lock rail made up of 'H' section, a uPVC hollow section of size 100x30 mm and 2 mm (± 0.2 mm) wall thickness fixed to the shutter styles by means of plastic/ galvanised M.S. 'U' cleats. The shutter frame filled with a uPVC multi-chambered single panel of size not less than 620 mm, having over all thickness of 20 mm and 1 mm (± 0.1 mm) wall thickness. The panels filled vertically and tie bar at two places by inserting horizontally 6 mm galvanised M.S. rod and fastened with nuts and washers, complete as per manufacturer's specification and direction of Engineer-In-charge.								
		1	1	1	2.10		1.00	2.10	
		2	1	1	1.50		1.20	3.60	
							Total	5.70	Sq.m
4	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade. 13.41.1 New work (two or more coats) over and including water thinnable priming coat with cement primer		Same item No.-2					279.36	Sq.m
5	A.C installation Charge							2.00	Nos
6	S/E TV cabinet							1.00	Nos
7	Curtains Channel	2							
8	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade								
	Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture	2	5		1.00		2.10	21.00	
		2	2		2.20		1.90	16.72	
		2	2		1.20		1.50	7.20	
								44.92	Sq.m

D.D.U. GORAKHPUR UNIVERSITY, GORAKHPUR

ABSTRACT OF COST

Detail of Measurement

Detailes of Measurement

S.No	Description of item	SCH.NO	Qty.	Unit	Rate DSR 2023	Multyplied by Rate Factor 0.735 in DSR 2023	Add Cost Index 111/107	Final Rate	Amount
1	9.105.3 66mm overall thickness Partition with 8mm thick double skin Calcium Silicate Board made with Calcareous & Siliceous materials reinforced with cellulose fiber manufactured through autoclaving	9.105.3	279.36	Sqm	2225.00	1635.38	61.14	1696.51	473945.32
2	9.117 9.118 Providing and fixing sliding arrangement in racks/ cupboards/cabinets shutter by with stainless steel rollers to run inside C or E aluminium channel section (The payment of C or E channel shall be made separately) Providing and fixing factory made uPVC door frame made of uPVC extruded sections having an overall dimension as below (tolerance ±1mm), with wall thickness 2.0 mm (± 0.2 mm), corners of the door frame to be Jointed with galvanized brackets and stainless steel screws, joints mitred and Plastic welded. The hinge side vertical of the frames reinforced by galvanized M.S. tube of size 19 X 19 mm and 1mm (± 0.1 mm) wall thickness and 3 nos. stainless steel hinges fixed to the frame complete as per manufacturer's specification and direction of Engineer In-charge								
	9.117.2 Extruded section profile size 42x50 mm	9.117.2	17.00	Rm	331.35	243.54	9.10	252.65	4294.99

3	9.118.2 30 mm thick factory made Polyvinyl Chloride (PVC) door shutter made of styles and rails of a uPVC hollow section of size 60x30 mm and wall thickness 2 mm (± 0.2 mm), with inbuilt decorative moulding edging on one side. The styles and rails mitred and joint at the corners by means of M.S. galvanised/ plastic brackets of size 75x220 mm having wall thickness 1.0 mm and stainless steel screws. The styles of the shutter reinforced by inserting galvanised M.S. tube of size 25x20 mm and 1 mm (± 0.1 mm) wall thickness. The lock rail made up of 'H' section, a uPVC hollow section of size 100x30 mm and 2 mm (± 0.2 mm) wall thickness fixed to the shutter styles by means of plastic/ galvanised M.S. 'U' cleats. The shutter frame filled with a uPVC multi-chambered single panel of size not less than 620 mm, having over all thickness of 20 mm and 1 mm (± 0.1 mm) wall thickness. The panels filled vertically and tie bar at two places by inserting horizontally 6 mm galvanised M.S. rod and fastened with nuts and washers, complete as per manufacturer's specification and	9.118.2	5.70	Sqm	3253.80	2391.54	89.40	2480.95	14141.39
4	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade 13.41.1 New work (two or more coats) over and including water thinnable priming coat with cement primer	13.41.1	279.36	Sqm	185.65	136.45	5.10	141.55	39545.15
5	A/C installation Charge	MR	2.00	Nos				7000.00	14000.00
6	S/F TV cabinet	MR	1.00	No				25000.00	25000.00
7	Curtains Channel	MR	80.00	Rm				350.00	28000.00
8	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade								
	Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture	13.62.1	44.92	Sqm	226.25	166.29	6.22	172.51	7749.16
					Total				606676.02
	Add 18% G.S.T.								109201.68
									715877.70
					Say (In Lacs)				7.16

Kaushlendra Gupta

[signature]