



कार्यालय-विश्वविद्यालय अभियन्ता,
दीनदयाल उपाध्याय गोरखपुर विश्वविद्यालय, गोरखपुर-273009 (उ०प्र०)

पत्रांक : 1054/वि०वि०अभि०/2025

दिनांक : 31/10/2025

अल्पकालीन निविदा सूचना

मा० कुलपति जी के प्राप्त आदेश के क्रम में एतद्वारा समस्त सम्बन्धित को सूचित किया जाता है कि विश्वविद्यालय परिसर में निम्नलिखित निर्माण/मरम्मत कार्य हेतु विश्वविद्यालय में पंजीकृत इस प्रकार के सम्पन्न कर रहे सिविल निर्माण/विद्युत मरम्मत कार्य से सम्बन्धित अद्यतन वैध रजिस्टर्ड ठेकेदारों द्वारा प्रतिशत दर पर निविदा आमंत्रित की जाती है।

क्रम सं०	कार्य का नाम	अनु०लागत (लाख में)	जमानती धनराशि (रुपये में)	कार्य पूर्ण कराने की समयावधि	निविदा का मूल्य + जीएसटी 18: + रु० 500.00 स्टेशनरी चार्ज (रुपये में)
1.	विश्वविद्यालय के अतिथि गृह शिवम ब्लॉक एवं चान्सलर ब्लॉक के पीछे इन्टरलॉकिंग का कार्य।	10.00	50,000.00	10 दिन	770.00
2.	विश्वविद्यालय परिसर में संवाद भवन से समाजशास्त्र विभाग तक क्षतिग्रस्त ओवर हेड लाइन मरम्मत व पोल लगाने का कार्य।	3.63	20,000.00	15 दिन	770.00
3.	प्रशासनिक भवन स्थित ट्रांसफार्मर से प्राणि विज्ञान शोध भवन के पोल तक 240 एम.एम. 3.50 कोर 78 मीटर विद्युत केबिल लगाने का कार्य।	1.785	9000.00	20 दिन	770.00

Kaushik Singh

Signature

कार्यालय-विश्वविद्यालय अभियन्ता,
दीनदयाल उपाध्याय गोरखपुर विश्वविद्यालय, गोरखपुर-273009 (उ०प्र०)



कार्यालय-विश्वविद्यालय अभियन्ता,

दीनदयाल उपाध्याय गोरखपुर विश्वविद्यालय, गोरखपुर-273009 (उ०प्र०)

12. विद्युत कार्य हेतु निविदादाता को निदेशक विद्युत सुरक्षा उ०प्र० लखनऊ के अन्तर्गत (ए) श्रेणी के पंजीकृत होना तथा निविदा के साथ नवीनतम प्रमाण पत्र संलग्न करना अनिवार्य है।
13. मरम्मत एवं आपूर्ति संबंधित कार्यों हेतु निविदादाता को इस तरह का कार्य का अनुभव होना अनिवार्य है।

निविदादाता को पैन कार्ड, जी०एस०टी०रजिस्ट्रेशन प्रमाण पत्रों की छायाप्रति संलग्न करना अनिवार्य है। अन्यथा निविदा मान्य नहीं होगी। निविदा खोलने के समय पंजीकरण, कार्य अनुभव संबंधी प्रमाण पत्र तथा पैन कार्ड, जी०एस०टी० रजिस्ट्रेशन संबंधी प्रमाण पत्र मूल रूप में प्रस्तुत करना अनिवार्य होगा। साथ ही संलग्न किये गये निविदा प्रपत्रों की स्व-प्रमाणित प्रति निविदा खोलने के समय प्रस्तुत करना होगा।

14. फर्म या ठेकेदार द्वारा प्रत्येक कार्य के लिए अलग-अलग निविदायें डाली जायेंगी। एक फर्म या ठेकेदार एक या एक से अधिक निविदायें डाल सकता है।
15. विश्वविद्यालय में पंजीकृत अद्यतन वैध रजिस्टर्ड ठेकेदारों को ही प्रतिभाग करने का अधिकार होगा।
16. विवाद की स्थिति में सभी विवाद गोरखपुर न्यायालय क्षेत्र में मान्य होगा।
17. अन्य विवरण एवं शर्तें अभियान्त्रिक कार्यालय दी०द०उ० गोरखपुर वि०वि० गोरखपुर से किसी भी कार्यदिवस में ज्ञात किया जा सकता है।
18. निविदादाता को इस आशय का शपथ पत्र देना होगा कि उसकी फर्म किसी सरकारी अथवा अन्य प्रतिष्ठित प्रतिष्ठान द्वारा ब्लैक लिस्टेड घोषित नहीं है।

Kamblendra Gupta

Signature

कुलसचिव

Signature



कार्यालय-विश्वविद्यालय अभियन्ता,
दीनदयाल उपाध्याय गोरखपुर विश्वविद्यालय, गोरखपुर-273009 (उ०प्र०)

तकनीकी बिड

1. कार्य का नाम
2. अनुमानित लागत
3. फर्म/ठेकेदार का नाम
4. पता
5. मोबाइल नम्बर
6. पंजीकरण का विवरण
(कृपया प्रमाण पत्र की छायाप्रति संलग्न करें)
7. धरोहर धनराशि का विवरण
(कृपया प्रमाण पत्र की छायाप्रति संलग्न करें)
एफ.डी./टी.डी.आर./एन.एस.सी.
बैंक का नाम
तिथि धनराशि
8. निविदा मूल्य का विवरण
(कृपया प्रमाण पत्र की छायाप्रति संलग्न करें)
एफ.डी./टी.डी.आर./एन.एस.सी./वि०वि० रसीद की संख्या
बैंक का नाम
तिथि धनराशि
9. जी.एस.टी. पंजीकरण का विवरण
(कृपया प्रमाण पत्र की छायाप्रति संलग्न करें)
10. पैन नम्बर
(कृपया प्रमाण पत्र की छायाप्रति संलग्न करें)
11. अनुभव संबंधी विवरण
(कृपया विवरण की छायाप्रति संलग्न करें)
12. ब्लैक लिस्ट न होने का शपथ पत्र
(कृपया विवरण की छायाप्रति संलग्न करें)
13. ज्यूडिसियल स्टाम्प पेपर पर इस आशय का उल्लेख कि निर्धारित समय के अन्तर्गत कार्य पूर्ण न करने पर धरोहर की धनराशि जब्त कर ली जायेगी।
(कृपया घोषणा पत्र की छायाप्रति संलग्न करें)
14. विद्युत संबंधी कार्य हेतु वांछित प्रमाण पत्र का विवरण
(कृपया साक्ष्य की छायाप्रति संलग्न करें)

हस्ताक्षर

फर्म/ठेकेदार का नाम

मुहर

Kaushikendra Gupta

Signature



कार्यालय-विश्वविद्यालय अभियन्ता,
दीनदयाल उपाध्याय गोरखपुर विश्वविद्यालय, गोरखपुर-273009 (उ०प्र०)

वित्तीय-बिड

क्रम सं०	कार्य का नाम	अनु०लागत (लाख में)	जमानती धनराशि (रुपये में)	कार्य पूर्ण कराने की समयावधि	निविदादाता द्वारा कार्य कराने हेतु सभी करों सहित दरें अंकित करें। (In percentage Below/Above)
1	विश्वविद्यालय के अतिथि गृह शिवम ब्लॉक एवं चान्सलर ब्लॉक के पीछे इन्टरलॉकिंग का कार्य।	10.00	50,000.00	10 दिन	

1. निविदादाता का नाम
2. पूरा नाम
3. पता
4. मुहर
5. मोबाइल नंबर
6. हस्ताक्षर

Kaushlendra Gupta

Trishank
Annet

D.D.U. GORAKHPUR UNIVERSITY, GORAKHPUR

ABSTRACT OF COST

Detail of Measurement

Details of Measurement

S.No	Description of item	SCH.NO	Qty	Unit	Rate DSR 2023	Multiplied by Rate Factor 0.735 in DSR-2023	Add Cost Index 111/107	Final Rate	Amount
1	Demolishing brick work manually by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. 15.7.4 In cement mortar	15.7.4	2.40	Sqm	2060.20	1514.25	56.61	1570.85	3770.06
2	Demolishing lime concrete manually by mechanical means and disposal of material within 50 metres lead as per direction of Engineer in-charge As per D.S.R. 15.1	15.10	12.33	Sqm	851.50	625.85	23.40	649.25	8003.94
3	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. 15.23.1 For thickness of tiles 10 mm to 25 mm	15.23.1	16.00	Cum	73.40	53.95	2.02	55.97	895.45
4	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead	15.56	325.00	Sq.m	54.65	40.17	1.50	41.67	13542.54
5	Concrete with 4.0 cm gauge brick ballast fine sand of 1:25 fineness modulus and cement in the proportion of 1:4:8 for foundation and under floors including supply of all materials labor and tools and plants etc required for proper completion of work.	4.1.2	26.00	Cum	6812.00	5006.82	187.17	5193.99	135043.76
6	Class 150 sub class A brick work in 1:4 cement & Coarse sand of 1:25 FM mortar in foundation and plinth including supply of all material labor T&P required for proper completion of the work.	6.1.1	7.50	Cum	7370.65	5417.43	202.52	5619.95	42149.61
	labor and tools and plants etc required for proper completion of work.	15.56	325.00	Sq.m	54.65	40.17	1.50	41.67	13542.54
	Concrete with 4.0 cm gauge brick ballast fine sand of 1:25 fineness modulus and cement in the proportion of 1:4:8 for foundation and under floors including supply of all materials labor and tools and plants etc required for proper completion of work.	4.1.2	26.00	Cum	6812.00	5006.82	187.17	5193.99	135043.76
	Class 150 sub class A brick work in 1:4 cement & Coarse sand of 1:25 FM mortar in foundation and plinth including supply of all material labor T&P required for proper completion of the work.	6.1.1	7.50	Cum	7370.65	5417.43	202.52	5619.95	42149.61

7	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M-30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer in-charge.	16.51.2	494.73	Sq.m	972.00	714.42	26.71	741.13	366657.90
8	12mm thick plaster in 1:6 with cement & fine sand of 1:25 FM mortar over brick work including raking the joints washing and cleaning & supply of all material labour T&P etc. required for the proper completion of the work.	13.4.1	325.00	Sq.m	357.35	262.65	9.82	272.47	88553.08
9	Finishing walls with Acrylic Smooth exterior paint of required shade 13.46.1. New work (Two or more coat applied @ 1.67 lit/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm).	16.51.2 13.46.1	494.73 650.00	Sq.m Sq.m	972.00 160.60	714.42 118.04	26.71 4.41	741.13 122.45	366657.90 79594.94
10	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. 5.22.1 Mild steel and Medium Tensile steel bars	5.22.1	805.63	Kg	107.10	78.72	2.94	81.66	65788.59
11	4.1.2 1:1.5:3 Cement 1:4 coarse sand (zone-III) derived from natural sources 3 graded stone aggregate 20 mm nominal size derived from natural sources	4.1.2	6.78	Cum	8340.85	6130.52	229.18	6359.70	43118.79
	Work done on above item applied	13.46.1	650.00	Sq.m	Total	118.04	4.41	122.45	847418.66
	Add 18% G.S.T.								152481.36
	exterior primer applied @ 2.20 kg/10 sqm								999600.01
					Say (In Lacs)				10.00
	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. 5.22.1 Mild steel and Medium Tensile steel bars	5.22.1	805.63	Kg	107.10	78.72	2.94	81.66	65788.59
11	4.1.2 1:1.5:3 Cement 1:4 coarse sand (zone-II) derived from natural sources 3 graded stone aggregate 20 mm nominal size derived from natural sources	4.1.2	6.78	Cum	8340.85	6130.52	229.18	6359.70	43118.79
	Work done on above item applied				Total				847418.66
	Add 18% G.S.T.								152481.36
									999600.01
					Say (In Lacs)				10.00